



Round Mountain Radio Ranch



Dayton Contest Forum May 2010

W2GD, K4ZA, NR5M

GOAL?

World-class multi-op station

with SOAB/SO2R capabilities

Driven by "Best of the Best" choices within station budget

> Quality Reliability LOUD All contributing factors!

Roadblocks in the way?

Property/station sat un-used nearly 15 years! (no maintenance)

Towers: 14 existing towers All showing serious neglect broken/missing guy wires vines over 40 feet high antennas and/or pieces dangling, or completely missing, etc.

Damaged 160M vertical



Damaged 15M stack tower

Damaged 10M stack tower

What was needed was a PLAN

We looked to experts! Consultations with W3LPL, N6BV, N3RD, K3LR, K4JA, & others, including our vendors... Choices? Keeping with "the best" factor...all K3LR/W3TX OWA Yagi stacks: 40M - 10M (48 ft booms)

All K0XG tower hardware, including star guy brackets & orbital ring rotators

All towers guyed w/Phillystran or Polygon Rod

All towers to be star-guyed to maximize capability/survivability

All Prosistel or K7NV-rebuilt Prop Pitch rotators

All Green Heron rotator controllers

Array Solutions Stack-Matches

All feed lines to be HELIAX

LDF-7 (1 & 5/8-in) running to tower bases LDF-5 (7/8-in) up towers for phasing lines LDF-4 feeding Beverages & 160/80M

Switching shed

Used for cable terminations orbital ring rotator power supplies matrix relay systems lightning protection/grounding

Then FSJ4-50 (1/2-in) SuperFlex in to hamshack

Order of work:

10M antennas (ARRL 10M Test to be 1st contest during station renovation)

then... 15M, 20M, 40M, 80M, 160M



the old Cutting loose (literally) old 40M KLMs



the new 40M 4L K3LR/W3TX OWAs @185/105ft w/ 10M OWA above



Typical construction approach—using a crane Safe, fast, labor-savings



Kenny, KZ5KG/W5AAC ranch resident, ground crew

Building M2 80M 3L Yagi #1 w2GD, K7ZV, K4ZA





3L 80M Yagi @ 135 ft

20M 6L OWA stack 44/94/144/198ft



15M 7L OWA stack 42/82/122/162ft



10M 8L OWA stack 35/70/105/140ft



6M 13L 60ft boom OWA stack 38/76/114/152ft



2M M2 EME array



NR5M PROJECT TIMELINE

May 2007 NR5M & W2GD meet in Dayton to discuss rebuild July 2007 Visit Texas—site survey Aug. 2007 develop preliminary reconstruction PLAN Sept. 2007 begin dismantling & guy repairs Oct. 2007 continue dismantling & begin 10M build & install Nov. 2007 continue 10M stack installation work Dec. 2007 finish 10M antenna installations Jan. 2008 begin 15M guy & rotator installation Feb. 2008 finish 15M stack installation Mar. 2008 begin 20M guy & rotator installation Apr. 2008 complete 20M guys, begin 40M guy work May 2008 finish 20M stack install, continue 40M guy & rotator work

Timeline, continued

June 2008 finish 40M stack/10M install, begin 80/160 antenna work July 2008 No Visit Aug. 2008 80M four square towers built & installed Sept. 2008 Complete 80M four squares, begin 160M Oct. 2008 Repairs after Hurricane Ike, finish 160M, begin 80M tower prep Nov. 2008 Build/Install 3L 80M wire Yagis, rotator maintenance Dec. 2008 Prep 135ft tower for 80M Yagi, Rotator Updates Jan. 2009 Finish 135ft tower prep, build 80M Yagi, repair 15M antennas Feb. 2009 No Visit Mar. 2009 install 1st 80M beam, add 80ft to 2nd 80M tower, start 6M tower repairs April 2009 No Visit

Timeline, continued

May 2009 6M & 185ft 80M tower guy wire & rotator work with K6NA June 2009 6M & 185ft 80M rotators, phasing lines, guys, feedline work July 2009 No Visit Aug, 2009 No Visit Sept. 2009 6M stack & 20M two-stack installs, XG rotator maintenance Sept. 2009 10M two-stack install 135ft 80M tower, 3L 80M install @ 185ft Oct. 2009 No Visit

Timeline, continued

Nov. 2009 XG rotator repairs, EME tower assembly Dec. 2009 No Visit Jan. 2010 LM-470 tower erected & 2M EME array installed Feb. 2010 15M mult tower w/TIC rings, cabling, 15M stack & 6M installs Apr. 2010 10M tower star guyed, VHF/UHF antennas installed

<u>Antennas in use May 2010</u>

160M 125 ft 25G vertical w/parasitic elements NE,NW,SW, SE **80M** pair Phased Four Squares 3L @ 185 ft <u>3L @ 135 ft</u> **40**M 4L/4L OWA @ 185/100 ft 4L OWA @ 80 ft

<u>20M</u>

6L/6L/6L/6L OWA @ 198/144/94/44 ft 6L/6L OWA @ 170/100 ft 4L @ 80 ft

15M 7I/7L/7L/7L OWA @ 162/122/82/42 ft 6L/6L KLM @ 105/65 ft 7L OWA @ 200 ft

<u>10M</u>

8L/8L/8L/8L OWA @ 140/105/70/35 ft 8L OWA @ 200 ft 9L/9L OWA @ 145/105 ft

VHF/UHF antennas All M2

2M 15L vert/hor @ 158 ft 23CM two stack 23CM35 @ 179 ft 432 two stack 13WL @ 163 ft 2M 12L @ 159 ft

What makes this project different?

Complexity... Duration... Logistics... Quality...

and of course...SIZE...

It's TEXAS...!

- You get the idea:
- It's big, BIGGER, BIGGEST!

Here's Don with some smaller stuff...

Practical matters..

• Star guying...



Beauty of star guys...



What to do with those LDF-5 phasing lines



HBX-56 (four square) insulators







3L 80M @ 185 ft



Supplies...





Switching shed

Beverage example



Beverage feedpoint detail



Solid rod tower for 80M two stack @ 340/170 ft

1296 EME array



16.5 ft dish

Brrrr....30-degrees in Texas?



Thank God for Wal-Mart!

Like what you've seen?

John Crovelli W2GD 908-391-5611 w2gd@hotmail.com

Don Daso K4ZA 704-408-7948 k4za@juno.com



Give us a call! We'd love to work for you~! Clearly...

BIG things are happening at NR5M

Here's George with more!





Crowded M-M operation

Contest Results

2007 ARRL 10M Mixed Mode #2 US/Canada

2008

ARRL SS S/O Phone #1 STX & #5 US/Canada ARRL SS Multiop CW #1 STX & #2 US/Canada ARRL DX 15M S/B SSB #1 US/Canada ARRL DX 15M S/B CW #1 US/Canada ARRL 10M SSB #1 STX IARU #1STX #2 US/Canada IOTA S/O SSB #3 World CQ WPX CW 15M S/B #1 US & #6 World CQ WPX CW 15M S/B #1 NA & #7 World CQ WW DX SSB #1 W5, #4 US & #19 World M/M 2009 ARRL 10M SO SSB 4th US/Canada RAC SOAB 1st World ARRL SS SSB SOHO 5th US/Canada ARRL SS CW Multiop 2nd US/Canada NA Sprint SSB SO 2nd US CQ WW CW MM 10th USA CQ WPX SSB SO/AB #1 W5 & #7 NA CQ 160M CW #1 W5, #7 US & #10 NA Russian DX SOAB Continental & US Winner

2010 CQ WPX SSB SOAB 4th US (Claimed scores) 160 SSB 4th US Russian DX SSB SO 9th World ARRL DX CW M-M 11th US NA Sprint SSB SO 2nd US BARTG Spring RTTY Multiop 3rd World NAQP SSB SO 3rd US RTTY M/S HP 1st World NAQP CW M2 1st US

Open Invitation to visit or operate at the ranch...



Wrap up...

Q&A?